

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
12/6/71
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Herman Johnson of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Century Oil Company,

Complete Address: 925 O. W. Garvey Building, Wichita, Kansas.

Lease Name: DeYoung Well No. 1

Location: SW-NE-NE Sec. 35 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3950' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

168'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 575'.

Circulate hole with heavy mud. Pull DP to 800' and displace 100 Sx.
cement thru DP. Pull DP to 180' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

H. L. Dickie
Conservation Division Agent