

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
12/2/74  
DEC 2 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Association,

Complete Address: P. O. Box #6, Great Bend, Kansas.

Lease Name: Van Loenen Well No. 3

Location: SW-SW-NE Sec. 11 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3837' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

195'--8 5/8" Surface casing, cement circulated.

3836'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3748'. Top perforations from 3534' to 3542'.

Sand well back to 3500' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent