

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-065-01523-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3/2/68
MAR 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jack Koron of Producers Oil Company has this date requested permission to plug the following described well:

Mr. Koron guarantees payment of the plugging fee.

Operator's full Name: Producers Oil Company,

Complete Address: 711 Philtower Building, Tulsa, Oklahoma.

Lease Name: Sandzen Well No. 1

Location: NE-SE-SW Sec. 11 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3860 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Koron was instructed to plug the well as follows:

237'--8 5/8" Surface pipe, cement circulated with 140 Sx.
3857'--5 1/2" Production casing cemented with 150 Sx. Well Plugged back to 3586'. Top perforations from 3560' to 3564'. Well squeezed @ 1270' with 250 Sx.

Sand well back to 3550' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 35 sacks gel plus 5 sacks hulls and 130 Sx. cement staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent