

State of Kansas



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3/6/68  
MAR 6 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Koron of Producers Oil Company has this

date requested permission to plug the following described well:

Mr. Koron guarantees payment of the plugging fee.

Operator's full Name: Producers Oil Company.

Complete Address: 711 Philtower Building, Tulsa, Oklahoma.

Lease Name: Sandzen Well No. B-2

Location: SE-NE-SW Sec. 11 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3863 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Koron was instructed to plug the well as follows:

216'--8 5/8" Surface pipe, cement circulated with 140 Sx.

3859'--5 1/2" Production casing cemented on bottom with 150 Sx. No plug back. Top perforations from 3568' to 3572'. 5 1/2" squeezed @ 1275' with 400 Sx. cement.

Sand well back to 3525' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 35 sacks gel plus 5 sacks hulls and 130 Sx. cement.

Very truly yours,

*M. L. Nicholi*  
Conservation Division Agent