

State of Kansas



15-065-01521-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
5/1/67
MAY 1 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this date requested permission to plug the following described well:

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Union Texas Petroleum,

Complete Address: Suite B-400, 1740 Broadway, Denver, Colorado.

Lease Name: Buss Well No. D--2

Location: SW-NW-SE Sec. 13 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3802 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

248'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3801'--5 1/2" Production casing cemented with 125 Sx. No per-
foration, no plug back.

Sand well back to 3790' and set 5 Sx. cement with dump bailer.

Squeeze well with 50 Sx. gel using 10 Sx. hulls in initial gel
and follow with 75 Sx. cement.

Very truly yours,

W. R. Nichols
Conservation Division Agent