

15-065-02194-00-01

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
8/10/67
AUG 10 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name: Denning Well No. 1

Location: SW-SW-NE Sec. 20 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3895 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

209' -- 8 5/8" Surface pipe, cement circulated.
3865' -- 5 1/2" Production casing cemented with 125 Sx. Top perforations @ 3687'. Dakota section from 1300' to 1500'.

Sand well back to 3650' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze with 10 Sx. gel followed with 100 Sx. cement then 20 Sx. gell, 20 Sx. cement 3 Sx. gel and 10 Sx. cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent