

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

10/17/63  
 OCT 7 1963  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co. has this

date requested permission to plug the following described well:

Morgenstern & Spectre Inc.

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Spectre, Inc.,

Complete Address: Box #661, Russell, Kansas.

Lease Name: Farrell Well No. 1

Location: NW-NW-SE Sec. 20 Twp. 9 Rge. (E) (W) 22


County Granam Total Depth 4098 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Lynch was instructed to plug the well as follows:

200'--8 5/8" Surface pipe, cement circulated.  
3950'--5 1/2" casing cemented with 125 Sx.  
Sand well back to 3935', and set 3 Sx cement with dump bailer.

Pull 5 1/2" to 600', circulate heavy gel mud and displace 20 Sx.  
cement thru 5 1/2". Pull 5 1/2" to 190' and displace 20 Sx cement  
thru 5 1/2". Pull 5 1/2", set rock bridge @ 40' and 10 Sx cement  
to bottom of cellar.

Very truly yours,  
  
 Conservation Division Agent