



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2/7/74
FEB 7 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Smith of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Ferrell Well No. 3

Location: CSE-SW Sec. 20 Twp. 9 Rge. (E)(W)22

County: Graham Total Depth 3900' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

188'--8 5/8" Surface casing, cement circulated with 145 Sx.
3899'--5 1/2" Production casing cemented on bottom with 150 Sx. Well
plugged back to 3838'. Top of perforations @ 3754'.

Push plug to 3700', sand well back to 3675' and set 5 Sx. cement with
dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks nulls, 30
sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Doherty
Conservation Division Agent