

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cus Tarbach of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Tarbach guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company, Incorporated,

Complete Address: 500 Bitting Building, Wichita, Kansas.

Lease Name: Stites Well No. 1

Location: CSW-MW Sec. 17 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3905' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Tarbach was instructed to plug the well as follows:

268'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 875'.

Circulate hole with heavy mud. Pull DP to 1100' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

A. G. Nichols
Conservation Division Agent