

State of Kansas



15-065-20034-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CORPORATION COMMISSION
7/31/67
JUL 31 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Roy Eckel of Peel-Hardman Oil Oprs., has this date requested permission to plug the following described well:

Mr. Eckel guarantees payment of the plugging fee.

Operator's full Name: Peel Hardman Oil Operators,

Complete Address: RR #3, Box #144-B, Wichita, Kansas.

Lease Name: Desair Well No. 5

Location: W/2-W/2-SE/4 Sec 26 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3777' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Eckel was instructed to plug the well as follows:

221'--8 5/8" Surface pipe, cement circulated with 235 Sx. Dakota section from 1350' to 1530'.

Circulate hole with heavy mud. Set plug thru DP from 1550' to 1250' with 100 Sx. cement. Pull DP to 210' and set plug thru DP from 210' to 150' with 20 Sx. cement. Pull DP set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent