



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2/17/74
FEB 7 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Smith of Rockhold Engineering, Inc. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Midwestern Supply Company, Incorporated.

Complete Address: 207 Brown Building, Wichita, Kansas.

Lease Name: Barber Well No. 1

Location: CNW-NE Sec. 27 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3921' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

267'--8 5/8" Surface casing, cement circulated with 165 Sx.
3919'--4 1/2" Production casing cemented on bottom with 175 Sx. No plug-
back indicated. Top perforations from 3603' to 3607'.

Push plug to 3550', sand well back to 3500' and set 5 Sx. cement with
dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25
sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent