

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
8/26/65
AUG 26 1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. John Crowe of Garvery Drilling Co., has this

date requested permission to plug the following described well:
Petroleum, Inc.,

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: 352 North Broadway, Wichita, Kansas.

Lease Name: Blakely Well No. 1

Location: App: NW-SW Sec. 30 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3915 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

226'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx. cement.

"	"	210' with $\frac{1}{2}$ sk. hulls &
		20 Sx. cement.
"	"	40' with $\frac{1}{8}$ sk. hulls &
		10 Sx. cement.

Very truly yours,

H. D. Nichols
Conservation Division Agent