

15-163-21234-00-00

3-30-89

289 R

6 070755

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 2-18-81
100' NW SE
_____, SEC. 4, T. 9 S, R. 19 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3255 Lease Name McClellan Well # 1

Operator: Christa Oil Company
Name & Address: Dean Ellner Inc. #2
25th and Vine
Hays, Ks. 67601
Rocks 113.25
Well Total Depth 3485 feet
Conductor Pipe: Size 0 feet
Casing: Size 8 5/8 feet 256

RECEIVED
STATE CORPORATION COMMISSION
4/6/89
APR 6 1989

SURVEILLANCE
CONSERVATION DIVISION
Wichita, Kansas

Abandoned Oil Well Gas Well Well SWD Well U&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing Co. License Number _____

Address East Hwy 40 Hays, Ks. 67601

Company to plug at: Hour: PM Day: 30 Month: Mar Year: 19 89

Plugging proposal received from Ted Luffers

(company name) Christa Oil Company (phone) 913-628-1909

were: 8 5/8" 256' S.P. cwc w/95 sks cement. 5 1/2" casing set at 3480' w/150 sks cement.

Perfs at 3434' - 3453'. Casing good. Possible squeeze on annulus. Proposal 300 sks
65/35 Poz 8% Gel 1/4# F.C. per sk. and 5 sks Hulls. Pumped in with pump truck. Perf casing
at 758' and 1435' loan both 5 1/2" casing and 5 1/2" and 8 5/8" annulus with cement. Shut in
under pressure.

Plugging Proposal Received *MJ* Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15PM Day: 30 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT Ordered 300 sks 65/35 Poz 8% Gel 1/4# F.C. per sack and 5 sks

Hulls pumped in with pump truck.

1. Perferated 5 1/2" casing at 758' and 1435'.
2. Annulus open pumped 200 sks cement in 5 1/2" casing w/6 sks Hulls mixed in.
3. Pumped 10 sks cement in annulus. Max pressure 300 psi. Ruptured casing.
4. Pumped an additional 110 sks in 5 1/2" casing, max pressure 900 psig. Shut in 500 psig.

Remarks: Cemented by Halliburton Cement
(If additional description is necessary, use BACK of this form.)

1. (old) observe this plugging.

DATE 4-19-89

INV. NO. 24326

Jib S

Signed *Marion J. Schmidt*
(TECHNICIAN)
Marion J. Schmidt