

15-163-21405-00-00

290

R

3-30-89

9-17-81

6 070754

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SE, SEC. 4, T 9 S, R 19 W/E

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3255

Lease Name McClellan Well # 2

Operator: Christa Oil Company

County Rooks 117.39

Name & Address Dean Ellner Inc. #2

Well Total Depth 3612 feet

25th and Vine Street

Conductor Pipe: Size 0 feet

Hays, Ks. 67601

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well Input Well SWD Well X U&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing Co. License Number

Address East Hwy 40 Hays, Ks. 67601

Company to plug at: Hour: AM Day: 30 Month: Mar Year: 19 89

Plugging proposal received from Ted Lubbers

(company name) Christa Oil Company (phone) 913-628-1909

were: 8 5/8" 249' S.P.L. cwc w/140 sks cement - 5 1/2" casing set at 3514' w/100 sks cement.

Perfs 3514' - 3619'. D.V. tool at 1382' circ. w/350 sks cement. Proposal 50 sks Class A

Cement and 300 sks 65/35 Poz 8% Gel w/1/4# of F.C. per sack and 5 sks Hulls. Loan and pressure bot

both annulus and 5 1/2" casing with cement. Shut in under pressure.

RECEIVED
STATE CORPORATION COMMISSION
4/16/89
APR 6 1989

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed at 11:40AM Day: 30 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT Ordered 50 sks Class A cement and 300 sks 65/35 Poz 8% Gel 1/4# of F. C. per sk and 5 sks Hulls. Pumped in with pump truck.

1. Pumped in 50 sks Class A cement followed with 275 sks 65/35 Poz 8% Gel w/1/4# lb. F.C. per sks and 3 sks Hulls. Max pressure 400 psig. Shut in at 250 psig. 5 sks in annulus 5 sks cement. 500 psig. Max pressure- and 250 psig, Shut in Cemented by Halliburton Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

DATE 4-19-89

INV. NO. 24327

Signed Marion J. Schmidt
Marion J. Schmidt