

12-30-91

2/R

4- 060287

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,656-00-00
50' W. of
NE SE SW /4 SEC. 34 , 09 S, 21 W
990 feet from S section line
3020 feet from E section line

Operator license# 5616 Lease Kuehnl well # 1

Operator: Calvin Noah County Graham

Address: 329 N. Birch Well total depth 3905 feet 126.91
Valley Center, Kansas 67147 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 237 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: Wichita, Kansas 67201

Company to plug at: Hour: 2:30A.M Day: 30 Month: December Year: 91

Plugging proposal received from: Harold Maley

Company: Abercrombie RTD, Inc. Phone: 316-262-1841

Were: Order 215 sxs. 60/40 pozmix - 6% gel. - 1/4# flocele per sx.
Space all plug with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 2:30A.M., Day: 30, Month: December, Year: 91

Actual plugging report:

- 1st. plug at 3850' with 25 sxs. - Arbuckle at 3560'.
- 2nd. plug at 1820' with 25 sxs. - Anhydrite at 1792' - 1831'.
- 3rd. plug at 1060' with 100 sxs. - Dakota 758' - 1058'.
- 4th. plug at 290' with 40 sxs. - Surface pipe to 237'.
- 5th. plug at 40' with 10 sxs.
- Rathole with 15 sxs.

RECEIVED

KANSAS CORPORATION COMMISSION
JAN 13 1992
1-13-92
CONSERVATION DIVISION
WICHITA, KS

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 2333 GL

I did [] / did not [X] observe the plugging.

(agent)

DATE 12-19-92

INV. NO. 34378

12-30

Gila S.