

7-1-87 15-065-01514-00-00

6 040169

API NUMBER 15- 2-16-53

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE SW, SEC. 34, T 9 S, R 21 (W/E)

feet from S section line

feet from E section line

Lease Name Koehn1 Well # 4

County Rooks Graham 125.61

Well Total Depth 3865 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 145' w/ circ. cmt

TECHNICIAN'S PLUGGING REPORT

Operator License # 6931

Operator: Bowman Oil Co.

Name & Address P.O. Box 37

Codell, Ks. 67630

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated -

Plugging Contractor Allied Cmtg. License Number

Address Russell, Ks.

Company to plug at: Hour: - Day: 1 Month: 7 Year: 19 87

Plugging proposal received from Don Bowman

(company name) Bowman Oil Co. (phone)

were: 5 1/2" csg set at 3861' w/ 100 sx cmt on bottom

Perf. in K.C. formation; D. V. at 1776' cmt w/325 sx.

pozmix and 80 sx stratocrite; Holes in csg. at 103' and

1247', tested w/tbg. and packer (sand fill-up in hole)

Ordered 200 sx 65/35 poz, 10% gel, 2% lite w/1/4" flo-cel and 6 sx hulls

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:15 PM Day: 1 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT Pumped in 100 sx lite w/ 1/4 # flo-cele and 4 sx.

hulls; blew hole in csg at surf.

Max 700 #

STATE CORPORATION COMMISSION
AUG - 7 - 87
1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 8-10-87

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

INV. NO. 17269
7-1

SEP 1 7 1987