

6 031478

1-24

1991
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-20677-00-01

C E/2 NW SE, SEC. 29, T 9 S, R 22 W/EX

1980 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5533

Lease Name Jeffers Well # 2

Operator: Arrowhead Pet. Inc.

County Graham 126.03

Name & Address Box 1393

Well Total Depth 3878 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 24th Month: Jan Year: 19 91

Plugging proposal received from Bill

(company name) Kelso (phone)

were: 8 5/8 set at 200 w/150 sks cwc. 4 1/2 set at 4873 w/125 sks. Perfs 3850 - 53

Order sand and common cement. Pull pipe. Order 250 sks 65/35 poz 10% gel .

.500 lbs. hulls Allied Cement Co. Honas water truck.

Ran bBailer to 1850 Hole open fluid level low.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45PM Day: 24 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 3800 w/4 sks common cement on sand w/

bailer shot off and recovered 1840 of 4 1/2 casing. Sq 8 5/8 w/250 sks cement blend

w/500 lbs. hulls mixed into max psi 450 lbs. Close in psi 200 lbs. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION
WICHITA, KANSAS

2-21-91
FFR 21 1991

INVOICED

DATE 2-25-91

INV. NO. 30855

[Signature]

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow