

10-4

386

6 040951

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-20,343 A 00-01
C N/2 S/SEC. 29, T 9 S, R 22 W/EX
SE/4 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5533
Operator: Arrowhead Pet Inc. Lease Name Jeffers Well # 1
Name & Address Box 1393 County Graham

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1988
CONSERVATION DIVISION
Wichita, Kansas

Address Great Bend, Ks. 67530
Total Depth 3876 feet
Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 207' w/140 sk
Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated
Plugging Contractor Halliburton Cement License Number
Address Hays, Ks.

Company to plug at: Hour: 9:00AM Day: 4 Month: Oct Year: 19 88

Plugging proposal received from A.D. Belt
(company name) Arrowhead Pet (phone)

were: 4 1/2" casing set at 3876' w/125 sks. Top perf at 3825' - 38'. Perf any
at 1925' and base Dakota at 1100'. Ordered 350 sks 60/40 Poz 8% Gel w/1/4# F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour 12:00 N Day: 4 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing 280 sks cement w/1/4# F.C. plus 3 sks Hulls
mixed in cement. Max 1000#. S.I. 900# Psi. Pumped 90 bbls slurry in 4 1/2" casing.
Pumped in 8 5/8" casing 70 sks cement w/1/4# F.C. plus 2 sks Hulls mixed in cement. Max
300#. S.I. 200# Psi.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-9-88
INV. NO. 22939

Signed Dennis L. Hamel
(TECHNICIAN)