

3-31

4-041958

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-163-20,628 0000

W2 W2 SE /4 SEC. 31, 08 S, 17 W  
1320 feet from S section line  
2310 feet from E section line

Operator license# 32250

Lease: Dopita Well # A-8

Operator: Kenny Brown Enterprises, LLC

County: Rooks 111.87

Address: P.O. Box 277  
Hays, Kansas 67601

Well total depth 3442 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 158 Feet  
W/125 sxs cmt.

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Cementing License# \_\_\_\_\_

Address: Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 31 Month: March Year 1998

Plugging proposal received from: Kenny Brown

Company: Kenny Brown Enterprises LLC Phone: \_\_\_\_\_

Were: 5 1/2" casing set at 3440' w/125 sxs cement. Perfs at 3042' - 3416'.  
Perf salt at 1750' - Anhy at 1320'. Hole in casing at 750'.  
Ordered 220 sxs Mid-Con II with 2% cl - 800# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 4:15 P.M., Day: 31, Month: March, Year: 1998

Actual plugging report: Perf casing at 1750' and 1320' with tubing in hole. At 1750' spotted 100 sxs cement with 400# hulls. Pulled tubing to 900' and spotted 90 sxs cement with 300# hulls to circulate at surface. P.O.O.H. with tubing and squeezed casing with 10 sxs cement. Max. P.S.I. 0#.  
8 5/8" S.P. Squeezed 30 sxs cement with 100# hulls. Max. P.S.I. 300#.

Remarks: \_\_\_\_\_

Condition of casing (in hole): GOOD \_\_\_\_\_ BAD X Anhy plug: YES X NO \_\_\_\_\_

Bottom plug (in place): YES \_\_\_\_\_, CALC X, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING X CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ G.L. \_\_\_\_\_

I did [ X ] / did not [ ] observe the plugging.

Denise J. Hamel  
(agent)

Form CP-2/3

**INVOICED**

DATE 4-21-98

INV. NO. 50366