

To: 6 041067  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-02 15-163-01371 *peck* 271  
E-19,172  
API NUMBER 15-  
C NW NW, SEC. 31, T 8 S, R 17 W/EX  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5386  
Operator: Production Drilling Inc.  
Name & Address: Box 680  
Hays, Ks. 67601

Lease Name Russ SWD Well # 2  
County Rooks 112.42  
Well Total Depth 3459 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1270' w/500

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well x SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cementing License Number \_\_\_\_\_  
Address Hays, Ks.

Company to plug at: Hour: 8:00AM Day: 2 Month: August Year: 19 89

Plugging proposal received from Larry Patterson  
(company name) Production Drilling Inc. (phone) \_\_\_\_\_

were: 5 1/2" casing at 3382' w/200 sks cement; 2" tubing at 2290' on packer;  
Top of tubing fish at 180'; top of casing fish at 155'.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 1:30PM Day: 2 Month: August Year: 19 89

ACTUAL PLUGGING REPORT Pumped 1000 gal. acid at 2 bbls min. w/beginning pressure  
at 500# psi. dropping to 50# psi at completion; followed w/200 sks common cement, pumped  
at 3 bbls per min w/pressure building to 750# psi. dropping to 400# at completion;  
followed w/300 sks 60/40 poz 6% gel pumped at 3 bbls per min. w/pressure to 400# and  
dropping to 200# at completion. Shut in psi 200#.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 0 1989 9/6/89

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.) Kansas

INVOICED  
did (or not) observe this plugging.

DATE 9-11-89  
INV. NO. 25876

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel