

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-03018-00-04

NW Sec. 31, T 8 S, R 17 W

660 feet from NS section line

660 feet from WE section line

SE/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name DOPITA Well # 1

Operator: HENNY BROWN
Name & Address ENTERPRISES

County ROOFS.

400 N. WASHINGTON
DRAWER 340
PLAINVILLE, MO. 67663

Well Total Depth 3386 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 101

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON CEMENTING License Number _____

Address 1100 EAST 8TH ST. HAYS, MO. 67601

Company to plug at: Hour: 9:30 AM Day: 3RD Month: MAY Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO HENNY BROWN

(company name) HENNY BROWN ENTERPRISES (phone) 913-434-4644

were: 8 5/8" 101ST SP. OUL. 10/60ST ENT, 5 1/2" BSG. SET @ 3386ST 100 ENT.

4 1/2" LINER SET @ 820^{FT}. THE DAWOTA WAS SQUEEZED BEFORE LINER WAS SET AND WOULDNT HOLD. MR. BROWN SAID THAT WELL WAS PLUGGED, AND HE RE-ENTERED WELL (OWWO) IN APPROX 1964. DRILLED CEMENT TO 820^{FT} WENT OUT OF HOLE AND ABANDONED. 4 1/2" LINER WAS CEMENTED IN ACCORDING TO MR. BROWN

Signed Marion Schmidt
(TECHNICIAN) (DOIC)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:25 AM Day: 3RD Month: MAY Year: 1983

ACTUAL PLUGGING REPORT

ORDERED, 300ST 50/50 Foz MIX 6% GEL-3% CA-CL, 4ST HULL'S. AND 4 1/2" PLUG. PUMPED IN WITH PUMP TRUCK.

PUMPED IN ANNULUS 100ST CNT AND 1ST HULL'S. MAX. PRESSURE 275^{PSI} SHUT IN AT 150^{PSI}, PUMPED IN 4 1/2" BSG. 65ST CNT. MAX PRESSURE 950^{PSI} SHUT IN @ 350^{PSI}

Remarks: CEMENTED BY HALLIBURTON CNT.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed Marion Schmidt
(TECHNICIAN) (DOIC)

RECEIVED
STATE CORPORATION COMMISSION
INVOICED
MAY 06 1983
DATE 5-11-83
V. NO. 4266-W
CONSERVATION DIVISION
Wichita, Kansas