

4-060669

4-5

15-163-03022-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 6-28-42

C NW NE /4 SEC. 31, 08 S, 17 W  
4620 feet from S section line  
1980 feet from E section line

Operator license# 4074

Lease Iruss well # 1

Operator: Innes Petroleum, Inc.  
Ron Innes  
Address: 229 East William  
O'Rourke Title Building  
Wichita, Kansas 67202

County Rooks

Well total depth 3389 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 1284 feet

110.14

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Northwest Well Service License#    

Address: Hill City, Kansas 67642

Company to plug at: Hour: 9:00A.M. Day: 5 Month: April Year: 95

Plugging proposal received from: Mike Vanausdale

Company: Northwest Well Service Phone: 913-674-2852

Were: Order 325 sxs. 60/40 posmix - 10% gel and hulls.  
Well open to TD - pulled tubing and rods on April 4, 1995 -  
good condition. Emergency permission to plug the well. F.L. 1300' from  
surface.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:30A.M., Day: 5, Month: April, Year: 95

Actual plugging report: 8 5/8" to 1284'. 5 1/2" to 3380'. Dug out  
wellhead and found cement in braden head. Perforated well at 825' -  
1325' and 1730'. Tied onto production casing and pumped 325 sxs. cement  
with 250# hulls. Max. P.S.I. 1300#. S.I.P. 400#.

Remarks: Halliburton Cementing.  
Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation: 1921 GL

I did [X] did not     observe the plugging.

**INVOICED**  
DATE 4-13-95  
INV. NO. 42572

4/12/95  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
APR 12 1995  
Form CP-2/3  
WICHITA, KANSAS