

6 040918

7-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-19034-0000
150' N SW NW NE
SEC. 31, T 8 S, R 17 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 6585

4400 feet from S section line

2310 feet from E section line

Operator: Kinderhook Oil and Gas

Lease Name Russ Well # 3

Name & Address Box 906 R. R. #2

County Rooks 110.83

Waukee, Iowa 50263

Well Total Depth 3410 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 210' cwc

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number

Address Plainville, Ks.

Company to plug at: Hour: 8:00AM Day: 7 Month: July Year: 19 88

Plugging proposal received from Laverne Steinle

(company name) Kinderhook Oil and Gas (phone)

were: 5 1/2" set at 3410' w/150 sks. Plug back at 3304'. Perf 3219' 21' and 3293' -95'.

Perf casing at 1325' w/3 holes, and 750' w/3 holes and 200' w/3 holes. Ordered 300 sks
65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus 600# Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15PM Day: 7 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 25 sks cement w/1/4# F.C. followed w/250

sks cement w/6 sks Hulls mixed in next 60 bbls. cement slurry. Max Psi 500# S.I. Psi

300#. Pumped in 8 5/8" S.P. 25 sks cement w/1/4# F.C. Max Psi 1000# S.I. 500# Psi.

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1988 10/21/88

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-25-88

INV. NO. 22695

7-7 NOV 15 1988

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis L. Hamel