

10-21-87

To: 6 070611
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-20,576-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5537
Operator: Kenneth O. Brown
Name & Address: Drawer 340
Plainville, Kansas 67663
Kenneth Brown

SW SW SE, SEC. 31, T 8 S, R17 W/E
feet from S section line
feet from E section line

Lease Name Dopita Well # A #7
County Rooks 111.64
Well Total Depth 3435 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 172

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing Co. License Number

Address 1100 East 8th Street Hays, Kansas 67601

Company to plug at: Hour: 10:00AM Day: 21 Month: Oct. Year: 19 87

Plugging proposal received from Kenneth Brown

(company name) Kenneth Brown Company (phone) 913-434-7236

were: 8 5/8" - 172' S.P. cwc w/150 sks cement. 5 1/2" casing set at 3434' w/150 sks cement.

Perfs at 3125' - 3403'; holes in casing 900' to 1100'; also, junk in hole. Open 250' tubing.

No pipe recovery. Casing squeezed at 750' w/250 sks cement; Proposal: 225 sks

Econolite 65/35 Pozmix 10% Gel and 5 sks Hulls, load and pressure both annulus and 5 1/2" casing with pump truck.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30PM Day: 21 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Ordered 225 sks Econolite 65/35 Pozmix 10% Gel and 5 sks Hulls.

Pumped in with pump truck. Pumped in annulus 50 sks of cement. 300 Psig.

Pumped in 5 1/2" casing 175 sks cement w/5 sks Hulls added in. Max Psig. 200. Shut in w/50 Psig. By Halliburton Co.

Remarks: The junk in the hole is 250' of open tubing at the bottom of the hole. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-8-87

INV. NO. 19195

Signed Marion J. Schmidt (TECHNICIAN) 12/7/87