

3-27

4-032214

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-163-20,773 0550

NE NW SW /4 SEC. 31 , 08 , 17 W
2310 feet from S section line
4290 feet from E section line

Operator license# 5537

Lease: Dopita Well # J-3

Operator: Kenny Brown

County: Rooks 112.78

Address: P.O. Drawer 340
400 N. Washington
Plainville, Kansas 67663

Well total depth 3470 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 171 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Service License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 27 Month: March Year: 1997

Plugging proposal received from: Kenny Brown

Company: Kenny Brown Phone: -

Were: Order 250 sxs 60/40 pozmix - 10% gel - 300# hulls.
Order work string.

4/9/97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:30 P.M., Day: 27 Month: March, Year: 1997

Actual plugging report: 8 5/8" set at 171' w/125 sxs. 5 1/2" set at 3469' w/175 sxs.
Prod. Perfs Arb. 3426' - 3430'. Ran tubing to 1900'. Pumped cement down tubing to circulate
with 200 sxs with 300# hulls mixed in. Squeezed 8 5/8" with 50 sxs cement. Old squeeze at
900' with 175 sxs at 750' with 250 sxs. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: GL

I observe the plugging.

Carl Goodrow
(agent)

DATE APR 09 1997

INV. NO. 47895