

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
3/6/68
MAR 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Producers Oil Company,

Complete Address 711 Philtower Building, Tulsa, Oklahoma.

Lease Name Sandzen Well No. 1

Location NE-SE-SW Sec. 14 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:30AM Day 2 Month 3 Year 1968

The above well was plugged as follows:

237'--8 5/8" Surface pipe, cement circulated with 140 Sx.

3857'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3586'. Top perforations from 3560' to 3564'. 5 1/2" squeezed @ 1270' with 250 Sx. cement.

Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 21 sacks gel plus 5 sacks hulls then 100 Sx. cement from 975' to 650', then 9 sacks gel from 650' to 250' and followed with 20 Sx. cement from 250' to 190', then 5 sacks gel from 190' to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure--200#. Final shut-in pressure--50#. (Cement-in and mudding operations performed by Allied Cementing Co. Inc.)

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INDEXED
DATE 3/6/68
INV. NO. 7369-W