

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE NW

SEC. 14 TWP. 9 RGE. 22

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease ~~SANZEN~~ Sandzen

Operator Sunray Midcontinent Oil Address Great Bend, Kans

Field _____ County Graham

Total Depth 3875 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 233' circulated with cement - 5 1/2" at 3852' with
125 sax cement behind.

P. B. to 3689', perforated at 3678', filled with sand to
3660', set 4 sax cement with dump bailer, pulled 3190' 5 1/2",
filled with mud to 220', set rock and 15 sax cement, mud to 35',
set rock and 10 sax cement to bottom cellar.

Edon Lee
District Conservation Agent

Date 4-28-56

RECEIVED
STATE CORP COM
5/2/56
MAY 2 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 14 T. 9 R. 22W
BOOK PAGE 54 LINE 41