

15-135-20535-00-00

SP

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
1/17/72
JAN 17 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling & Petroleum Resources

Complete Address Box 18407 Wichita, Kansas 67218

Lease Name Dinges "B" Well No. 2

Location NW SE SE Sec. 16 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4535' - 56.69

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30 P Day 11 Month 1 Year 1972

The above well was plugged as follows:

RTD 4535' 8 5/8 csg set at 316' cwc. Cmt. Mat. 50-50 poz W/4% added gel.

Gurned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messing
Well Plugging Supervisor

DATE 1-18-72

INV. NO. 5073-W