

15-065-01522-00-00

Form CP-3
Rev. 6-9-67

KANSAS

24

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3/6/68
MAR 6 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Producers Oil Company,

Complete Address 711 Philtower Building, Tulsa, Oklahoma.

Lease Name Sandzen Well No. B-2

Location SE-NE-SW Sec. 14 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3863

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 11:30 AM Day 2 Month 3 Year 1968

The above well was plugged as follows:

216'--8 5/8" Surface pipe, cement circulated with 140 Sx.
3859'--5 1/2" Production casing cemented on bottom with 150 Sx. No plug back, Top perfor-
ations from 3568' to 3572'. 5 1/2" squeezed @ 1275' with 400 Sx. cement.

Pushed plug to 3550' and sanded well back to 3525' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 21 sacks gel plus 5 sacks hulls and

followed with 100 Sx. cement from 975' to 650' then 9 sacks gel from 650 to 250' and

followed with 20 Sx. cement from 250' to 190' then 5 sacks gel from 190' to 40' and

finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure--250#.

Final shut-in pressure--100#. (Mudding and cementing operations performed by Allied
Cementing Co. Inc.0.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 3/6/68
INV. NO. 9370-W