

15-127-00067-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. NE NE NW

LOCATION NE cor. NW

SEC. 26 TWP. 16 RGE. 5E

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. ONE(1) Lease Willms

Operator Koester & Mergen Address 302 Orpheum Bld'g, Mc Pherson, Ks

Field Wild Cat County Morris

Total Depth 2312 Feet.

(Describe briefly the manner in which the well was plugged)

This well was plugged at the bottom with heavy mud taken from the rotary pits and poured in the hole from 2312 ft back up to 2200 ft. The hole was then bridged at 185 ft. with a 15 foot rock and mud bridge, and then cemented with 12 sacks of cement. Then bridged again at the top, and cemented again with 3 sacks of cement. There was 2261 ft. of 5 3/8" set in this hole and all was pulled out. There was 168 ft. of 8-5/8" surface pipe set, cemented that was left in the hole.

PLUGGING
FILE SEC. 26 TWP. 16 RGE. 5E
BOOK PAGE 28 LINE 45

SEARCHED
SERIALIZED
4/11/51
APR 11 1951

[Signature]
District Conservation Agent

Date 4-9-51

F