

15-127-00068-00-00

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 57-11

LOCATION SWc NE SE

SEC. 26 TWP. 16 RGE. 5E

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. TWO (2) Lease Peterson

Operator Koester & Mergen Address 302 Orpheum Bld'g, Wichita, Kas.

Field 3 Mile Creek County Morris

Total Depth 2292 Feet.

(Describe briefly the manner in which the well was plugged)

This well was plugged from the bottom(2292 ft.) up to
2215 ft. with heavy mud taken from the rotary pits, and
poured in the hole. The hole was then bridged at 185 ft.,
with a 15 foot rock and mud bridge; and then cemented with
12 sacks of cement. Then bridged again a few feet from the
top, and cemented again with 3 sacks of cement. There was
2236 ft. of 4 1/2" pipe cemented with 25 sacks, set in this hole
that was ripped off at 2146 ft. There was 157 ft. of
surface pipe set, cemented, that was left in the hole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 26 TWP 16 RGE 5E
BOOK PAGE 57 LINE 11

J. Peterson
District Conservation Agent
Date January 25, 1951