

15-127-19010-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 3-20

LOCATION SE SE SE

SEC. 26 TWP. 16 RGE. 5E

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. Four(4) Lease Peterson

Operator Koester & Mergen Address 302 Orpheum Bld'g, Wichita, Kas

Field 3 Mile Creek County Morris

Total Depth 2306 Feet.

(Describe briefly the manner in which the well was plugged)

This well was plugged at the bottom with heavy mud from  
2306 ft. back up to 2206 ft. The hole was then bridged at  
200 ft. with a 15 ft. rock and mud bridge. Then cemented  
with 12 sacks of cement. Then bridged a few feet of the  
top and cemented with 5 sacks of cement. There was 2234 ft of  
5 1/2" set; that was ripped off at 2210 ft. There was 178 ft of  
8-5/8" surface pipe set, cemented, that was left in the hole.

3/28/52

District Conservation Agent

Date March 26, 1952.

**PLUGGING**  
FILE SEC. 26 T. 16 R. 5E  
BOOK PAGE 3 LINE 20