

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2/17/74
FEB 7 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Ferrell Well No. 3

Location CSE-SW Sec. 20 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 12:00 M Day 4 Month 2 Year 1974

The above well was plugged as follows:

188'--3 5/8" Surface casing, cement circulated with 145 Sx.

3899'--5 3/8" Production casing cemented on bottom with 150 Sx. Top of cement @ ??

Well plugged back to 3830'. Top perforation @ 3754'.

Pushed plug to 3700', sanded well back to 3650' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing (723') and squeezed well initially with 5 sacks hulls and 15 sacks

gel and followed with 110 Cu. Ft. cement from 1025' to 700' then 12 sacks gel from 700'

to 220' and followed with 30 Cu. Ft. cement from 220' to 145' then 3 sacks gel from

145' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-

in pressure-300#. FSIP-100#. (Mudding and cementing operations by Allied Cmtg. Inc.,).

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Dickel
Well Plugging Supervisor

INVOICED
DATE 2/8/74
INV. NO. 8532-W