

15-065-01521-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

*24*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
5/1/67  
MAY 1 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum,

Complete Address: Suite B-400, 1740 Broadway, Denver, Colorado.

Lease Name Buss Well No. D-2

Location SW-NW-SE Sec. 13 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth Union Texas--3802'  
Authority 5800'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Santa Fe Pipe & Supply, Incorporated.

Address: Box #562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 11:00AM Day 24 Month 4 Year 1967

The Above well was plugged as follows:

248'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
3801'--5 1/2" Production casing cemented with 125 Sx. No plug back, no perforations indicated.

Sanded well back to 3790' and set 5 Sx. cement with dump bailer.

Squeezed well with 47 Sx. gel using 6 Sx. hulls in initial gel and followed with 75 Sx. cement. Maximum pump-in pressure 400#, Final shut-in pressure 150 #. (Mudding and cementing operations by Globe).

(Recovered 1123' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. R. Nichols*  
Well Plugging Supervisor

DATE 5/1/67

INV. NO. 5138-W