

15-065-02194-00-01

Form CP-3
Rev. 6-26-62

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
8/10/67
AUG 10 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box # 797, Great Bend, Kansas.

Lease Name Denning Well No. 1

Location SW-SW-NE Sec. 20 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3895

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 346

Operation Completed: Hour 11:30 Day 8 Month 7 Year 1967

The Above well was plugged as follows:

209'--8 5/8" Surface pipe, cement circulated.
3865'--5 1/2" Production casing cemented with 125 Sx. Top perforations @
3687'. Sand back to 3650' and set 5 Sx. cement with dump bailer.
Dakota section from 1300' to 1500'.

Sanded well back to 3650' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" casing. Squeezed well with 7 Sx. gel plus 1 sack hulls then followed
with 100 Sx. cement then 20 Sx. gel followed by 30 Sx. cement then 3 gel
followed with 20 Sx. cement. Maximum pump-in pressure 400#. Final shut-
in pressure 150#. (Mudding and cementing performed by Sun Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. A. Nichols
Well Plugging Supervisor

DATE 8/10/67
INV. NO. 6109-W