

15-065-20105-00-00

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1967
12/6/67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Alpine Oil & Royalty Company, Incorporated.
Complete Address 800 Bitting Building, Wichita, Kansas.
Lease Name Brandyberry Well No. 2 B-1
Location NW-SW Sec. 17 Twp. 9 Rge. (E) (W) 22
County Graham Total Depth 3895
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Gabbert-Jones, Incorporated.
Address 830 Sutton Place, Wichita, Kansas. License No.
Operation Completed: Hour 10:00 PM Day 29 Month 11 Year 1967

The above well was plugged as follows:

226'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1275' to 1475'.
Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1175'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from
240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 12/6/67
INV. NO. 6848-W