

15-065-19142-00-00 4-22-87

6 030867

API NUMBER 15- 5/27/55

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SE, SEC. 33, T 9 S, R 21 W/E
2910 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568
Operator: Kaiser-Francis Oil Co.
Name & Address: P.O. Box 21468
Tulsa, Oklahoma 74121-1468

Lease Name Bragg Well # 9 SWD
County Graham 140.21
Well Total Depth 4314 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 189

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B.J. Titan License Number _____
Address Hays, Kansas

Company to plug at: Hour: AM _____ Day: 22 Month: April Year: 19 87

Plugging proposal received from John Glenn

(company name) Kaiser - Francis (phone) _____

were: 8 5/8 set @ 189 W/125 sx 5 1/2 set @ 3995 W/200 sx open hole 3995-4314 PBTD-4270

Perf @ 1800' W /300 sx perf @ 1400 W/50 sx Order 300 sx econolite 6 sx hulls. B.J. Titan

Cmt Co: Sundowner Water Trucks

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:AM Day: 22 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT Mix and pump down 5 1/2 " csg 50 sx cmt slurry (25bbl)

Followed w/247 sx cmt mix (124 bbl cmt slurry)

Pumped on back side w/3 bbl. cmt slurry locked up 500 #

Closed in @ 150# 5 1/2" csg went on vac will refill later.

Cement dropped 581'. This was ready mixed 4-29-87 to surface

RECEIVED
STATE CORPORATION COMMISSION
5/11/87

Remarks: _____
(If additional description is necessary, use BACK of this form. Wichita, Kansas)

INVOICED (If not observe this plugging.

DATE 5-15-87

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 16908 4-22

JUN 1 1 1987 JUL 0 8 1987