

031388

7-10

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE SE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 12- 065-22-520-0001
SEC. 26 T 9 S. R 21 W/8

3630 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Cox Well # 1

Operator: _____
Name & Address _____
Midwestern Pipeworks, Inc.

County Graham 126.10

Address _____
Box 1199

Well Total Depth 3880 feet

_____ Hays, Ks. 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 5/8 feet 214

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling License Number _____

Address Great Bend, Ks.

Company to plug at: Hours _____ PM Days: 10 Month: July Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing (phone) _____

were: 8 5/8 set at 214 w/135 sks cwc. 5 1/2 set at 3452 w/65 sks. 4 1/2 set at 3880

w/125 sks. Perfs 3813 - 30 PBT 3870. Order sand and common cement.

Pull pipe, order 250 sks 65/35 poz. 8% gel 500 lbs. hulls. Allied Cement Co.

Roll OWS water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00AM Day: 10 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3760 w/5 sks common cement on sand w/bailer

Recovered 1317 of casing.

Sq 8 5/8 w/250 sks cement blend w/500 lbs. hulls mixed in to max psi 500 lbs. Close in

psi 200 lbs. Plug complete.

Remarks: _____

INVOICED (if additional description is necessary, use BACK of this form.)
(did / did not) observe this plugging.

DATE 7-24-90

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 28722

Carl Goodrow

7-10 SEP 14 1990