

6 070773

S-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,520-00-00
NE SE NW, SEC 28, T 9 S, R 21 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5465

Operator: John B. Collins
Name & Address: DBA B. J. Oil Company
1503 Suite B
Hays, Ks. 67601

3630 feet from S section line
2970 feet from E section line

Lease Name Cox Well # 1

County Graham 125.13

Well Total Depth 3850 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Western Ks. Drilling License Number _____

Address 2700 Oak Hays, Kansas 67601

Company to plug at: Hour: AM Day: 26 Month: May Year: 19 89

Plugging proposal received from Frank Taggart

(company name) Western Ks. Drilling (phone) _____

were: 8 5/8" 210' S.P., cwc w/135 sks 60/40 poz 3% gel 2% ca cl. By Halco

Elv. 2291' Anhy 1730' No cir problems, mud condition 44 vis. 9.8 weight. Arb 3810'. Proposal 215 sks 60/40 Poz 6% Gel and 8 5/8" plug. Spot with drill stem, circulate, heavy mud between all plugs. 25 sks at 3750' - 25 sks at 1740' - 100 sks at 1015' - 40 sks at 260' - 10 sks at 40' 15 sks rathole (circulate)

RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1989
6/13/89
MARION J. SCHMIDT
TECHNICIAN

Plugging Proposal Received by Marion J. Schmidt

Plugging Operations attended by Agent?: All _____ None _____

Operations Completed: Hour: 2:30PM Day: 26 Month: May Year: 19 89

ACTUAL PLUGGING REPORT W.K.D. Ordered 215 sks 60/40 poz 6% gel and 8 5/8" plug.

Spotted with drill stem circulated heavy mud between all plugs. 1st plug at 3750' w/25 sks cement. 2nd plug at 1740' w/25 sks cement. 3rd plug at 1015' w/100 sks and w/1 sk f.c. 4th plug at 260' w/40 sks cement. 5th plug at 40' w/10 sks cement and 8 5/8" plug. 15 sks in rathole. Cemented by Allied Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
I (bid) / contractor observe this plugging.

DATE 6-14-89

INV. NO. 25055

Signed Marion J. Schmidt
Marion J. Schmidt
TECHNICIAN