

9-29

4-031860

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-01498-00-00

S2 NE NW /4 SEC. 26, 09 S, 21 W
4620 feet from S section line
3300 feet from E section line

Operator license# 5363

Lease Cox A well # 3

Operator: Berexco, Inc.

County Graham

Address: Box 723
Hays, Kansas 67601

Well total depth 3812 feet ^{123.89}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 187 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Berexco, Inc. License# 1530
Address: Hays, Kansas 67601 Rig Tag

Company to plug at: Hour: P.M. Day: 29 Month: September Year: 93

Plugging proposal received from: George Jorgensen

Company: Berexco, Inc. Phone:

Were: Order 300 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Shot @ 1770' below salt.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:15P.M., Day: 29, Month: September, Year: 93

Actual plugging report: 8 5/8" set @ 187' w/120 sxs. cwc. 5 1/2" set @ 3805' w/75 sxs. 4 1/2" liner set @ 1818' cwc w/75 sxs. 1119' w/150 sxs. 890' w/150 sxs. - 770' w/75 sxs. cwc. O.H. 3805' - 3812'. Solid cement with braden head in 8 5/8" annulus. Ran tubing, spotted 50 sxs. cement blend. Laid down tubing to 900' circulated cement blend to surface. Laid down tubing squeezed 4 1/2" with total 300 sxs. cement blend w/500# hulls mixed in to Max. P.S.I. 400#. Close in P.S.I. 150#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did [X] / did not [] observe the plugging.

INVOICED

OCT 05 1993

DATE

INV. NO. 3887.3 ⁹⁻²⁹

Carl Goodrow
(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
OCT 04 1993
10/4/93
CONSERVATION DIVISION
Wichita, Kansas