

4-061002

15-065-02567-00-01

D-04,090

11-25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 6-54

SE SE NE /4 SEC. 26, 09 S, 21 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 5363

Lease Cox A Well # 2

Operator: Berexco, Inc.

County: Graham 126.26

Address: P.O. Box 723  
Hays, Kansas 67601

Well total depth 3885 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well\_\_\_, Gas well\_\_\_, Input well\_\_\_, SWD X, D & A\_\_\_

Plugging contractor: Co Tools License# -

Address: \_\_\_\_\_

Company to plug at: Hour: 10:00 A.M. Day: 25 Month: November Year: 1996

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 400 sxs 60/40 posmix - 10% gel and hulls.  
Tubing to top of fish.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 1:45 P.M., Day: 25, Month: November, Year: 1996

Actual plugging report: 8 5/8" to 217' w/135 sxs. 5 1/2" to 3872' w/100 sxs. Pulled tubing and fished tubing to below 1300'. Well open and on a strong vacuum. Perforated at 1040' and ran tubing to top of fish. Circulated cement to surface with 145 sxs with hulls. Pulled tubing. Tied onto annulus and pumped 50 sxs cement with 50# hulls. S.I.P. 50#. Tied onto production casing and pumped 255 sxs cement with hulls. Max. P.S.I. 500#. S.I.P. 100#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES \_\_\_\_\_, CALC X, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING X, CASING \_\_\_\_\_ Elevation: 2197 GL

I did [ X ] observe the plugging.

*[Signature]*  
DX (agent)

DATE DEC 05 1996

INV. NO. 47111