

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22818-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 35-9S-21W
830 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: DEYOUNG Well Number: 1
County: GRAHAM Total Vertical Depth: 3900 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B WEST 10TH STREET
GREAT BEND, KS 67530

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 252
Production: Size feet:
Liner: Size feet:

\$126.75

Well Type: DH UIC Docket No: Date/Time to Plug: 06/18/2001 6:15 AM

Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.

Proposal Rcvd. from: DORAN MARKHEIM Company: L.D. DRILLING, INC. Phone: (316) 793-3051

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 06/18/2001 9:15 AM

WitnessType: Plugging Operations Were Not Witnessed
KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3835' w/25 sxs. Arbuckle 3837'.
2nd. Plug at 1775' w/25 sxs. Anhydrite 1747' - 1780'.
3rd. Plug at 1025' w/100 sxs. Dakota 701' - 1001'.
4th. Plug at 305' w/40 sxs. Surface pipe to 252'.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

INVOICED
DATE 6-20-01
NO. 2001061970


RECEIVED
KANSAS CORPORATION COMMISSION
JUN 20 2001
CONSERVATION DIVISION

Remarks: LEASE READS AS FOLLOWS: 160'S.OF NWSWSW 35-09-21W. ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)