

4-041698

7-13

15-065-03001-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15- - 1956

NE NW SE /4 SEC. 14, 09 S, 22 W  
2310 feet from S section line  
1650 feet from E section line

Operator license# 5310  
Operator: Four-Way Operating, Inc.  
Address: Box 698  
Great Bend, Kansas 67530

Lease: Sandzen Well # 3  
County: Graham 124.18  
Well total depth 3821 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8% Inch @ 222 feet  
W/125 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing License# -

Address: Oberlin, Kansas 67749

Company to plug at: Hour: 8:30A.M. Day: 11 Month: July Year 1995

Plugging proposal received from: Jim Rockhold

Company: Four-Way Operating, Inc. Phone:

Were: 5 1/2" casing set at 3815' w/150 sxs cement. Perf at 3483' - 3777'  
Anhy. @ 1780' - Dakota @ 1010' - Casing squeeze at 2752' w/300 sxs and 1103' w/225 sxs.  
Ordered 400 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
7/27/95  
JUL 27 1995

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

CONSERVATION DIVISION  
WICHITA, KANSAS

Completed: Hour: 3:45 P.M., Day: 13, Month: July, Year: 1995

Actual plugging report: Perf casing on July 10, 1995. R.I.H. with tubing to 1900'. Spotted 200 sxs cement with 400# hulls to circulate cement to surface. P.O.O.H. with tubing. Hook-up to 5 1/2" casing - squeezed 50 sxs cement. Max. P.S.I. 500#. S.I.P. 400#. Hooked-up to 8 5/8" S.P. Squeezed 50 sxs cement with 100# hulls. Max. P.S.I. 400#. S.I.P. 300#.

Remarks:  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC X, NO  
Plugged through TUBING X, CASING. Elevation: 2298 GL

I did [ X ] / did not [ ] observe the plugging.

INVOICED  
DATE 7-31-95  
INV. NO. 43219

Dennis L. Hamel  
(agent)