

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01520-00-00
Spot: CNENESE Sec/Twnshp/Rge: 13-9S-22W
2310 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: BUSS D Well Number: 1
County: GRAHAM Total Vertical Depth: 3797 feet

Operator License No.: 31008
Op Name: BOWMAN, PAUL OIL
Address: 801 CODELL ROAD
CODELL, KS 67663

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 237
Production: Size 5.5 feet: 3796
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/22/2001 12:00 PM

Plug Co. License No.: 31008 Plug Co. Name: BOWMAN, PAUL OIL

Proposal Rcvd. from: PAUL BOWMAN Company: BOWMAN, PAUL OIL Phone: (785) 434-2633

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing squeezed at multiple intervals from 700' to 2700' with 3700 sxs cement.
Fish in hole below 2750'.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 02/22/2001 2:00 PM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Ran tubing to 2650' - spotted 15 sxs gel followed with 60 sxs cement with 200# hulls mixed in cement.
Pulled tubing to 1600' - spotted 80 sxs cement to circulated at surface.
Pulled tubing and filld casing to surface with 10 sxs cement.
RU cementers to 8 5/8" S.P.
Squeezed 25 sxs cement with 100# hulls mixed in cement.
Max. P.S.I. 100#. S.I.P. 100#.

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 2001
CONSERVATION DIVISION
Wichita Kansas

INVOICED

DATE 03-08-2001

INV. NO. 2001061466

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

ANDERSON-PRICHARD OIL CORP #1 BUSS D

13-9-22W

NE NE SE

Contr. GLENN PEEL DRILLING COMPANY

GRAHAM

County

E 228 LRB Comm. Comp. 9-21-51 IP 144 BOPD (ARB LM)

PHY POT.

Tops	Depth	Datum
HEEB	3447	-1163
LANS	3486	-1202
ARB	3795	-1511
T.D.	3797	-1513

Casing

5" 3796

DST 3480-3545, 30 MIN.

734' SLIGHT GAS CUT

WTR, SHOW FREE OIL,


3' FREE OIL:

DP: CO 3797

SWB 7 BQPH/16 HRS:

PMP 115 BQ/24 HRS.

MOREL POOL



237' - 8 5/8

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

3796-3800