

6-100411

5-30

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,578-00-00

NE SW NE /4 SEC. 20, 09 S, 22 W  
3630 feet from S section line  
1650 feet from E section line

Operator license# 5533

Lease Denning well # 1

Operator: Arrowhead Petroleum, Inc.

County Graham

Address: P.O. Box 8237 - Munger Station  
Wichita, Kansas  
67208

Well total depth 3840 feet <sup>124.80</sup>  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 265 feet

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: Duke Drilling Company License# 5929

Address: Wichita, Kansas 67202

Company to plug at: Hour: ?? Day:        Month:        Year:       

Plugging proposal received from: Jay Schneider

Company: Duke Drilling phone:       

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 1910 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1100 feet " 100 " Mousehole:        sacks

3rd plug @ 310 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sacks

Plugging Proposal Received by:       

Plugging operations attended by agent? All[        ], Part[        ], None[ X ]

Completed: Hour: 4:45 am, Day: 30, Month: May, Year: 1990

Actual plugging report: Hole reported plugged as above.  
Order 190sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2355 GL, Anhydrite depth: 1907 - 1947 feet

Did NOT penetrate Arbuckle, cemented by Allied

I did[    ] / did not[ X ] observe the plugging.

**INVOICED RECEIVED**  
STATE CORPORATION COMMISSION

David K. Wann

David K. Wann P.I.R.T. II  
(agent)

DATE: 8-28-90 8/22/90  
NOV 22 1990

INV. NO. 28132  
CONSERVATION DIVISION  
Wichita, Kansas