

4-060599 10-24

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-20,105-00-01

C NW SW /4 SEC. 17, 09 S, 22 W
1980 feet from S section line
4620 feet from E section line

Operator license# 5363

Lease Brandyberry ^{KCC CAP} ~~OWWO~~ well # 1

Operator: Berexco, Inc.

County Graham

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 3895 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 228 feet

126.58

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License# _____

Address: _____

Company to plug at: Hour: 12:30 P.M Day: 24 Month: October Year: 94

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: Ordered 325 sxs. 60/40 posmix - 10% gel and hulls.
Plug through tubing.
Perf. at 1950' and 2380'.
Dakota broke in.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 4:45 P.M., Day: 24, Month: October, Year: 94

Actual plugging report: 8 5/8" to 228' w/150 sxs. 5 1/2" to 3703' w/75 sxs. Tubing sanded in below 3199'. Tubing to top of fish at 3180'. Pumped 75 sxs. cement with 200# hulls. Pulled tubing to 2080' and pumped 75 sxs. cement with 100# hulls. Pulled tubing to 981' and pumped 50 sxs. with 200# hulls. Pulled tubing to 490' and pumped 50 sxs. cement with cement to surface. Pulled tubing. Tied onto annulus and pumped 50 sxs. cement. Max. 50# P.S.I. S.I.P. 50#. Tied onto production casing and pumped 25 sxs. cement. No pressure due to bad casing in sands.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL _____

I did did not observe the plugging.

DATE 11-2-94

INV. NO. 41554

10-24 JAN 19 1995

[Signature]
AH (agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
10/31/94
OCT 31 1994
CONSERVATION DIVISION
WICHITA-KANSAS