

5-15 4-032235

15-065-00317-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1950

SE SE SW /4 SEC. 23, 09, 22 W
330 feet from S section line
2970 feet from E section line

Operator license# 31274

Lease: Germany Well # 1

Operator: R.L. Hrbek

County: Graham 127.47

Address: Rt. 1 - Box 11
Merino, CO 80741

Well total depth 3922 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 238 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 15 Month: May Year: 1997

Plugging proposal received from: R.L. Hrbek

Company: R.L. Hrbek Phone: -

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order sand and common cement.

6/3/97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3:45 P.M., Day: 15 Month: May, Year: 1997

Actual plugging report: 8 5/8" set at 238' cwc. 5 1/2" set at 3908'. Prod. Perf. 3756'-3760'. PBTB 3816'. Recovered 350' of 5 1/2" with shots at 1829' - 1050' - 800'. Mixed and pumped down 5 1/2" - 70 sxs cement blend with 400# hulls to circulate. Pulled casing and topped off with 15 sxs cement blend. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

INVOICED
DATE JUN 06 1997

Carl Goodrow
(agent)

INV. NO. 48236 Form CP-2/3
5-15 JUL 22 1997