

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,731-00-00

C NW NE, Sec. 35, T 31 S, R 11 W/4

660 feet from N/S section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Smith Well # 4-35

Operator: Hummon Corporation
Name & Address 400 One Main Place
Wichita, Kansas
67202

County Barber

Well Total Depth 3860 feet 125.45

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Big H Drilling Inc License Number 5148

Address 400 One Main Place Wichita Kansas 67202

Company to plug at: Hour: 3:00am Day: 11 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Jerry Thorp

(company name) Big H. Drilling Inc (phone) _____

were: To Fill hole with heavy mud + spot plugs through drill pipe
1st plug @ 810' w/50sx, 2nd plug @ 270' w/40sx
3rd plug @ 40' w/solid Bridge plug + 10sx, Circulate
10sx in the Rathole, Circulate 10sx in the mousehole,
Using 60/40 poz mix 2%ogel 3%cc

Signed Richard M. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:50am Day: 11 Month: January Year: 1984

ACTUAL PLUGGING REPORT Fill hole with heavy mud + spot plugs through drill pipe
1st plug @ 810' w/50sx, 2nd plug @ 270' w/40sx
3rd plug @ 40' w/solid Bridge Plug, + 10sx, Circulate
10sx in the rathole, Circulate 10sx in the mousehole
using 60/40 poz mix 3%ogel 3%cc

Remarks: Sen pumped the cement

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE OF KANSAS
11/18/84
JAN 18 1984
CONSERVATION DIVISION
Wichita, Kansas
INVOICED
DATE 1-20-84
INV. NO. 9207 W

Signed Richard M. Lacey
(TECHNICIAN)