

1060138

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,763-00-00

C SW NW, Sec. 35, T 31 S, R 11 W
1980 feet from N/X section line

TECHNICIAN'S PLUGGING REPORT

660 feet from W/X section line

Operator License # 5148 Lease Name Chapin Well # 2

Operator: Big-H Drilling, Inc.
Name & Address: 400 One Main Place
Wichita, KS 67202
County Barber

Well Total Depth 3862 feet 125.51

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Company Tools License Number 5148

Address 400 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 1:00 am Day: 28 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Jerry Tharp

(company name) Big-H (phone) 316-264-7726

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 800' with 50 sx cement

2nd plug at 270' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement.

6th plug to circulate mousehole with 10 sx cement.

Signed Paul A. Luthie
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 am Day: 28 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 800' with 50 sx cement, 2nd plug at 270' with

50 sx cement. 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to

surface with 10 sx cement. Circulate rathole with 15 sx cement. Circulate

mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3% cc. by Sun Cementing.

RECEIVED
STATE CORPORATION COMMISSION
2/2/84
FEB 02 1984
Conservation Division
Wichita, Kansas

I hereby certify that the above plugging instructions were given as given and stated
and that I (XXX / did not) observe this plugging.

Signed Paul A. Luthie
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INV 2103 D
2-6-84
REV. NO. 0065
1-28