

1020163

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,929-00-00  
150' East of  
C SW SW, SEC. 35, T 31 S, R 11 W/X  
660 feet from ~~XXX~~ SE Corner of N section line  
4515 feet from ~~XXX~~ SE Corner of W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Smith Well # 7-35

Operator: Hummon Corporation

County Barber

Name & Address 400 One Main Place

Well Total Depth 3860 125.45 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big H Drilling, Inc. License Number 5148

Address 400 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 30 Month: September Year: 19 84

Plugging proposal received from Jerry Tharp

(company name) Big-H (phone) 316-263-8521

were: \_\_\_\_\_ to fill hole with heavy mud and spot cement through drill pipe

1st plug at 810' with 50 sx cement

2nd plug at 270' with 50 sx cement  
solid bridge

3rd plug hulls + plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:00 pm Day: 30 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 810' with 50 sx cement, 2nd plug at 270' with 50 sx cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
10/5/84  
OCT 05 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

If additional description is necessary, use BACK of this form.  
I, \_\_\_\_\_, did not observe this plugging.

Signed [Signature] SWD  
(TECHNICIAN)

INVOICED

DATE 10-8-84

INV. NO. 4133